Wasco County SWCD Cost Share Program Application

ATTENTION: It is the responsibility of the applicant/landowner to obtain any required permits for the project being cost shared. If you need assistance contact the SWCD office.

Applicant Name Carver Livestock LLC	
Address	-
Phone &	
PROJECT DESCRIPTION Please include a detailed map of the project area ar	nd budget to summarize expenses.
12 Digit HUC: 170701060201	SWCD LRP Priority Ranking#
NRCS Practice Code: 430	NRCS Practice: Migation Pipeline
Is this project Ag Water Quality Related?	ODA Management Area:

1. Project Proposal – Please describe the resource concern, what will be done & who will do the work.

At our Wolf Run property we irrigate 40a of alfalfa with valid water rights. We utilize ditch water, and store it in two ponds, for when the ditch flow drops. This works as a cistern to gather water between cuttings. When the ditch water runs low, we pump out of our lower pond, and refill it via gravity from the upper one. During high ditch flow, or when hay is being cut, we refill the ponds. The upper pond and pipeline between them, was nrcs approved when built a decade ago. The existing 3" pipeline in a gravity situation doesn't keep up with the rate of depletion when irrigating out of the lower pond. We need to replace the 3" pipe with 6"ADS pipe, to fully utilize the upper ponds water storage purpose.

We will do the work ourselves. The pipeline is 1600'. Pipe is around \$8/ft \$12,800
Backhoe work at \$120/hr. 50 hours \$6000
Total project cost is \$18,800

2. Describe how this project will address the resource concern or provide an overall benefit that this project will provide to the watershed.

This project will benefit the watershed by increasing the utilization of our existing water. Using the water we have onsite will decrease the amount of water that needs to be diverted from eight mile creek to satisfy the water rights and crop needs. This project also fixes a miscalculation from a previous water conservation project.

Estimated Total Cost: \$ Amount Requested: \$	18,800 7,500	Project Start Date: Completion Date:	9-1-24 1-1-25
Amount Requested.	(50%, UP TO \$7,500)	Completion Date	1-1-23
Black Con	_	-	6-19-24
Applicant Signature		Date	
Staff Reviewmgrtech	_adm Recommend: Fund N	lot Fund Board Action: A	pproved / Denied
		Date:	

79771 WOLF Run Rd.

The Blue line is the proposed pipeline upgrade. 1600

Rattle Snaki creek

Carver Livestock LLC – Irrigation Pipeline

Before Photos





